

# New Standards of Validation Equipment

NOEL C. BASCO, JR.

European Certified-SPT, DGSV, SGSV, RN, CSSYB

October 26, 2019

#### **Objectives:**

At the end of the session, participants will be able to...

- Understand what is validation
- ☐ Know the ways of validation the sterilization equipment.

#### **Validation**

A process that consists of systematically carrying out the process in a specific manner in order to improve by planning.

Usually applies to equipment or procedures used for reprocessing medical devices.

Establish temporary programmes and checklists, validation protocols with criteria for acceptance/rejection, resource needs and risk analysis.

#### Validation should consist of the following:

- 1. Installation Qualification (IQ)
- 2. Operational Qualification (OQ)
- 3. Performance Qualification (PQ)
- 4. Documentation
- Microbiological Performance Qualification (MPQ)
- 6. Validation report and certificates



#### Installation Qualification (IQ)

A process of obtaining and documenting evidence that equipment has been provided and installed in accordance with its specification.





#### Steps of IQ:


1. Verify correct installation of connections




#### **Technical Data Sheet**









Integrated steam supply, steel pedestal or feets and side panelling are accessoires

| Data fo | or the dimensioning of the s | anitary and electrical installations on site   |  |   |
|---------|------------------------------|--|--|---|
| A       | Drain<br>with pedestal       | Temp. max. 55° C (in case of failure<br>100° C for a short period of time)<br>With integrated steam generator  | Connection<br>Discharge<br>Discharge         | DN 70<br>15 l/min<br>45 l/min               |
| A1      | Drain<br>with feet           | Temp. max. 55° C (In case of fallure<br>100° C for a short period of firme)<br>With integrated steam generator | Connection<br>Discharge<br>Discharge         | DN 50<br>15 l/min<br>45 l/min               |
| DL      | Compressed alr               | PA 5-10 bar  | Connection Design capacity Consumption appr. | DN 15<br>15 Nm <sup>3</sup> /h<br>0.2 Nm³/h |
|         |                              | With integrated steam generator  | Consumption appr.                            | 0.4 Nm <sup>3</sup> /h                      |
| E       | Electric mains               | 3/N/PE 400 V AC, 50 Hz   | Power  | 3.0 kW                                      |
|         | Not applicable in            | Connecting cable Offlex (YSLY-J)   | Fuse protection                              | 10 A  |
|         | case of connected            | 5x2,5 mm2. Main switch to be provided  | Consumption/h appr                           | 1.2 kWh                                     |
|         | steam generator              | on site  |  |   |
| EW      | Softenend Water              | PA 3-5 bar, Remaining hardness <0.1" d   | Connection                                   | DN 15                                       |
|         | Opt, jacket cooling          | Temp, max, 15° C   | Design capacity                              | 1,2 m <sup>3</sup> /h                       |

#### Compressed air

#### PA 5-10 bar

|          | steam generalor                   | equivalent device. Noncondensable gases   | Percentage   | ≤3.5%                          |
|----------|-----------------------------------|---|--|--------------------------------|
| KW       | Fresh water                       | Temp. max. 15° C, 3-15° d, PA 3-5 bar   | Connection<br>Design capacity<br>Consumption appr. | DN 15<br>1.4 m³/h<br>0.2 m³/h  |
| Addition | al data concerning electric steam | generator (optional)  |  |                                |
| ABBL     | Blow-off pipe<br>for safety valve | Galvanized steel pipe for blowing the<br>steam off into the open up to 0.35 bar<br>max. back pressure at 185 kg/h flow  | Connection   | DN 40                          |
| DW       | Demineralized fresh<br>water      | 1-5 μS/cm, PA 1-5 bar   | Connection<br>Design capacity<br>Comsumption appr. | DN 15<br>0.25 m³h<br>0.028 m³h |
| EK       | Electric mains                    | 3/NIPE 400 V AC, 50 Hz Only flexible cable allowable Officx (YSLY-J) 5x25 mm <sup>2</sup> Provide load break switch on site close to the unit. We recommend a load break switch with remote disconnection, potential free contact provided in the unit. | Power<br>Fuse protection<br>Consumption/h appr.    | 48 kW<br>80 A<br>12 kWh        |
|          | Remote disconnect.                | Connecting cable  | 1x YSLY-0  | 2x0.75 mm²                     |

#### Steps of IQ:

2. Verify the correct operation of the equipment's different security functions, according to standards.

DATE : 06/02/09

PROCESS START : 12:34:56 STERILIZER NAME : L20074

STERILIZER NUMBER: 1

CYCLE COUNTER : 200

SIGNALS

AI03 CHAMBER PRESSURE
AI27 S CHAMBER PRESSURE

AIOO CHAMBER TEMP

AI24 S CHAMBER TEMP

AI01 JACKET TEMP

**PARAMETERS** 

STERIL TEMP 121.0 C

STERIL TIME 00:20:00

POST VACUUM TIME 00:05:00

PROGRAM: P1 POROUS LOAD

| PROGTIME<br>START | AI03  | AI27  | AI00 | AI24 | AI01  |
|-------------------|-------|-------|------|------|-------|
| 00:00:00          | 1.008 | 1.007 | 45.0 | 45.1 | 118.9 |
| 00:00:10          | 1.011 | 1.010 | 45.1 | 45.1 | 118.5 |
| 00:00:20          | 1.016 | 1.015 | 45.2 | 45.2 | 118.2 |
| PREVACUUM         |       |       |      |      |       |
| 00:00:20          | 1.016 | 1.015 | 45.2 | 45.2 | 118.2 |
| 00:00:30          | 0.855 | 0.781 | 48.6 | 50.2 | 117.9 |

#### Steps of IQ:

3. Confirm that the machine is equipped with technical documentation.

Installation plans
Technical/Operational User Manual



## Operational Qualification (PQ)

A process of obtaining and documenting evidence that the installed equipment operates within predetermined limits when used accordance with its operational procedures.



#### Aim:

- 1. To verify that the sterilizer's different measurement and control element function correctly and within the ranges specified by the manufacturer.
- 2. To verify that the temperature distribution in the chamber is uniform and within the parameters designated by the country standards.

1. Calibration of the regulation and control elements




2. Carry out a cycle with the vacuum test.



3. Carry out a cycle with the Bowie-Dick Test



4. Implement three thermometric tests in an empty chamber in order to obtain the temperature profile at all points of the chamber



#### Performance Qualification (PQ)

A process of obtaining and documenting evidence that the equipment as installed and operated is in accordance with operational procedures consistently performs in accordance with predetermined criteria and thereby yields a product meeting its specification.



#### Tests must include:

- 1. Reference load that corresponds to the routine load.
- 2. Packaging systems that corresponds to the routine packaging system.
- 3. Load configuration specified and known to be the most difficult to sterilize- worst case.
- 4. Volume and weight.

| Qualification                | Responsible Person              |
|------------------------------|---------------------------------|
| 1. Installer Qualification   | The installer                   |
| 2. Operational Qualification | The installer/<br>User/Operator |
| 3. Performance Qualification | User/Operator                   |



### Thank you!

